

TARGET 4.3KM

BILL NO. 1: PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES					
ITEM	DESCRIPTION	UNIT	QTY	RATE(KSHS)	AMOUNT(KSHS)
	Brought forward from previous page.				
1.01	Allow a Prime cost of KShs. 50000 for supervision	PC Sum	PC	50,000	50,000.00
1.02	Provide, erect and maintain publicity signs as directed by the Engineer	No.	2		
	Total carried forward to summary page				

BILL NO. 8: CULVERTS AND DRAINAGE WORKS					
	Note: No separate payments shall be made for gravel for blinding or hauling to spoil unsuitable excavation materials and the cost of such shall be included in the rates and prices				
8-60-01	culvert installation 600mm: Bed class 15/15, Wing walls , apron, Head wall and toe beam class 20/20,with surround class 20/20 and end structures reinforced with BRC A142 mesh including backfilling with approved material At aic chemwabul-kaptagat	M	21		
	Bill No. 8 Total Carried Forward to Grand Summary				

BILL NO. 10: GRADING AND GRAVELLING WORKS					
	NOTE: No overhaul will be paid for separately under these items as it shall be deemed to have been included in the Contractor's rates				
10-50-004	Heavy grading	m ²	20,000		
10-70-002	Provide gravel wearing course-excavation,free haul,spread and compact gravel to a thickness 150mm	cm	355		
	Bill No.10 Total Carried Forward to Grand Summary				

GRAND SUMMARY OF BILL OF QUANTITIES		
BILL ITEM	DESCRIPTION	AMOUNT (Kshs)
	NOTE;ALL PRICES ARE VAT INCLUSIVE	
1	Preliminaries and General Items	
8	Culverts and drainages	
10	grading and gravelling	
(A)	SUB-TOTAL (1)	