

BQ FOR KIPLEGETETWO WATER PROJECT - TAMBACH WARD WATER PROJECTS 2017/2018 FY**EXTENSION OF DISTRIBUTION TO KIPTORO VILLAGE**

ITEM NO	DISCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Clear the bush 1m wide along the pipeline route	M	1680		
2	Supply ,handle, lay and test 25mm G.I class B pipeline as per Engineers specification	M	1680		
3	Supply, fix and test 25mm G.I union socket	NO	15		
4	Supply, fix and test 25mmX15MM G.I Tee	NO	4		
5	Construct anchor blocks/support pillars as per Engineers specification	NO	5		
6	Supply and deliver to site barbed wire gauge of 400m long for intake site fencing	No	2		
7	Sign post	Item	L/S		
8	Supervision, monitoring and evaluation	item	L/S	50.000	50,000
	GRAND TOTALS				