

**SAMBIRIR WARD**

**KOIBATEK WATER PROJECT 2017-18**

**PIPELINE (Nyirar Tobongon line)**

<b>Item</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
01	Excavate and backfill trench minimum 600mm deep in normal soil	M	4518		
02	Provide and lay 40mm Ø GS pipe class B for river crossing and exposed area. Use approved jointing compound.	No	50		
03	Provide, handle, lay and joint 40mm PVC pipe class D using approved jointing compound(Tangit solvent cement)	No	703		
05	Provide and install the following fittings for places to be specified by the Engineer. <ul style="list-style-type: none"> <li>• 40mmØ PVC adaptor</li> <li>• 40mmØ plain socket</li> <li>• 40mmØ union socket</li> <li>• 40mmØ 90° GS bend</li> </ul>	No No No No	12 6 4 4		
05	Provide and fix 40mmØ washout at lowest section along the line between Nyirar and Tobongon schools.	No	1		
	<b>Sub Total to be carried to grand total</b>				
<b>06</b>	<b>add</b> Project supervision	<b>L/S</b>	<b>1</b>	<b>75,000</b>	<b>75,000</b>
<b>07</b>	<b>Add</b> Project signage	<b>L/S</b>	<b>1</b>		
	<b>GRAND TOTAL TO BE CARRIED TO FORM OF TENDER</b>				

**AMOUNT IN WORDS (KSHS)**.....  
.....  
.....

**CONTRACTOR’S NAME**.....

**ADDRESS**.....

**SIGN**.....

**STAMP**.....