

TAMBACH WARD 2017/2018 FY

NGEMBA CHEPTILE:SETEK AND KAPTERIK WATER PROJECTGRAVITY MAIN LINE

TAMBACH WARD

ITEM	DISCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Clear bush 1m wide along the pipeline route	M	978		
2	Fabricate, supply fix and test 200mm x100mm G.I Reducing Tee, drilled and flanged all sides complete with associated fittings	NO	1		
3	Fabricate 200mm stainless plate to act as a cap for 200mm G.I Tee.	ITEM	L/S		
4	Supply, fix and test 100mm G.I bends	NO	4		
5	Supply, fix and test 100mm G.I sluice valve	NO	1		
6	Supply, fix and test 100mm G.I flanges(paired)	NO	8		
7	Supply, handle ,lay ,joint and test 100mm G.I Class B pipeline	M	978		
8	Supply, fix and test 25mm G.I double acting air valve	NO	1		
9	Construct anchor block/support pillars 400mm x 400mm x 1000mm	NO	10		
10	Construct valve chamber1200mm x1200mm x1000mm	NO	2		
11	Sign post	NO	1		
12	Supervision, monitoring and evaluation	ITEM	L/S	80,000	80,000
GRAND TOTAL TO BE CARRIED TO FORM OF TENDER					

AMOUNT IN WORDS (KSHS).....

CONTRACTOR'S NAME.....

ADDRESS.....

SIGN.....

STAMP.....