

BILLS OF QUANTITIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
<u>ELEMENT 01: SUBSTRUCTURES</u>					
<u>(All Provisional)</u>					
<u>Excavations for Ramp trenches</u>					
A	Excavate foundation trench not exceeding 1.5 m deep starting from stripped level actual depth for excavation to be determined on site	8	CM		
B	300mm thick approved hardcore filling consolidated and rolled in layers not exceeding 150mm thick.	4	CM		
<u>Murram Blinding</u>					
C	50mm thick murram blinding to surfaces of hard-core	15	SM		
<u>Anti termite treatment</u>					
D	"Termidor" or equal Insecticide treatment to surface of blinding with 10 year guarantee	15	SM		
<u>Concrete Class 20/20 (1:2:4) in ;</u>					
E	150mm ramp	15	SM		
<u>Steel Fabric Reinforcement</u>					
F	B.R.C Mesh Reinforcement type A142 weighing 2.22 KG/SM with minimum 300 mm end and side laps.	15	SM		
<u>Sawn Formwork to;</u>					
G	Edge of Ramp 75-150mm wide.	12	LM		
<u>Foundation Walling</u>					
H	200mm thick Quarry stone walling bedded and jointed in cement sandmortar (1:3) and reinforced with 16gauge hoop iron at alternate course	15	SM		
<u>Damp proofing</u>					
J	1000 gauge damp proof membrane laid with minimum 300 mm side and end laps	15	SM		
<u>Plinths</u>					
K	Render and set 12 mm thick cement and sand (1:4) plaster on plinth	26	SM		
L	Prepare and apply three coats gloss emulsion paint to rendered surfaces externally	26	SM		
Totals for Element 01 carried to summary					

BILLS OF QUANTITIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT 02: SUPERSTRUCTURES</u>				
	<u>All Provisional</u>				
	<u>Gable Walling and Eaves Filling</u>				
A	200mm fair faced quarry stone walling bedded and jointed in cement sand mortar (1:4) to approval reinforced with hoop iron gauge 16 at every alternate course.	35	SM		
	<u>Total for Walling carried to Summary</u>				

BILLS OF QUANTITIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT 04: DOORS</u>				
A	<u>2400x2400mm high folding steel casement panelled door complete with hinges, stays, fasteners, permanent vents with mosquito gauze and sheet metal hood etc assembled and fixed to opening including cutting and pinning lugs to concrete or blockwork surround and bedding frame in cement-sand mortar (1:4)</u>	1	NO		
	<u>Painting</u>				
B	Prepare and apply undercoat and three coats gloss oil paint on surfaces internally	6	SM		
C	Ditto externally	6	SM		
D	Rubber Door stoppers plugged to floor with 38mm rag bolt	2	NO		
	<u>Carried to Summary</u>				

BILLS OF QUANTITIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT 05: FINISHES</u>				
	<u>Floor Finishes</u>				
A	<u>Floor</u> 12mm Thick cement sand simple screed ready to receive terrazo finish to approval	122	SM		
B	18mm Thick terrazo floorn finish polished with coloured finish to approval	122	SM		
C	100mm wide ditto as skirting	58	LM		
D	32x3mmthick plastic divided strips	124	LM		
	<u>Walls Internally</u>				
E	12mm thick Gauged plaster comprising 9mm thck c/s mortar (1:4); 3mm thick cement lime (1:1) steel trowelled to approval	148	SM		
F	Prepare and apply undercoat and three coats gloss oil paint on plastered surface.	148	SM		
	<u>Externally</u>				
G	12mm thick Gauged render comprising 9mm thck c/s mortar (1:4); 3mm thick cement lime (1:1) steel trowelled to approval	148	SM		
H	Prepare and apply undercoat and three coats gloss oil paint on rendered surface.	148	SM		
J	1200x600x50mm thick precasted paving slabs on well compacted quarry dust to approval	62	SM		
	<u>Carried to Summary</u>				

BILLS OF QUANTITIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT 05: ROOFING & RAINWATER GOODS</u>				
	<u>Roof sheets</u>				
A	28 gauge prepainted IT4 Profiled sheets with bolt and rubber washers	180	SM		
	<u>Ridge Cap</u>				
B	28 gauge ridge cap to match	14	LM		
	<u>Downpipes</u>				
C	GI Downpipes 100mm diameter including brackets and shoe to approval	24	LM		
	<u>Gutters</u>				
D	225x150x325mm ms gutter to approval	32	LM		
	<u>Paint</u>				
E	paint to ditto	15	SM		
	<u>All structural steel members should have welded and bolted joints and should be approved by the Engineer</u>				
F	Internal members 50x30x2.5mm thick RHS	264	LM		
G	Rafters 80x40x3mm thick RHS	124	LM		
H	ZED Purlins 150x50x3mm thick 14gauge	172	LM		
	<u>Carried to Summary</u>				

BILLS OF QUANTITIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>BUILDING WORK SUMMARY</u>				
A	Element 01: Substructure				
B	Element 02: Walling Superstructure				
C	Element 03: Doors				
D	Element 04: Finishes				
E	Element 05: Roofing and Rainwater goods				
	GRAND TOTAL				

BILLS OF QUANTITIES

ITEM	DESCRIPTION	AMOUNT
<u>PROVISIONAL AND PRIME COST SUMS</u>		
A	Provide P.C sum for Electrical works	100,000.00
B	Provision for Lightning arrestors	40,000.00
C	Provide erection of Signboard with signage to approval	40,000.00
SUMMARY FOR PRIME COST SUMS		180,000.00

BILLS OF QUANTITIES

ITEM	DESCRIPTION	AMOUNT
GRAND SUMMARY		
A	Building Summary from EMC/7	
B	Provisional and P C Sums from EMC/8	180,000.00
C	SUB TOTALS	
D	Contigencies	100,000.00
E	Project Management	50,000.00
GRAND TOTAL		

GRAND TOTAL CARRIED TO FORM OF TENDER

*** Note that prices quoted are inclusive of all taxes**

CONTRACT PERIOD.....WEEKS

CONTRACTOR'S NAME.....

ADDRESS.....

SIGN.....

DATE.....

STAMP.....