

EMC ROADS DEPARTMENT 2017-2018 PROJECT. MAINTENANACE OF BUNGWET- CHEBARA VTC ROAD IN MOIBEN KUSERWO
WARD

TARGET: 1.6KM

ITEM	DESCRIPTION	UNIT	QTY	RATE(KSHS)	AMOUNT(KSHS)
BILL NO. 1: PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES					
1.01	Allow a Prime cost of KShs 25,000 for supervision	LS	1	25,000	25,000.00
1.02	Provide, erect and maintain publicity signs as directed by the Engineer	No.	1		
Total carried forward to summary page					
BILL NO. 4: SITE CLEARANCE AND TOPSOIL STRIPPING					
04-50-004	Light Bush Clearing	SM	1,125		
Bill No. 4 Total Carried Forward to Grand Summary					
BILL NO. 8: CULVERTS AND DRAINAGE WORKS					
	Note: No separate payments shall be made for gravel for blinding or hauling to spoil unsuitable excavation materials and the cost of such shall be included in the rates and prices				
08-60-020	New Culvert Installation-600mm Hounded, With aprons, wingwalls, headwalls and toe beam reinforced with BRC A142 MESH	M	7		
Bill No. 8 Total Carried Forward to Grand Summary					
BILL NO. 10: GRADING AND GRAVELLING WORKS					
10-70-002	Provide gravel wearing course- excavation free haul, spread and compact gravel to 150mm thick.	CM	420		
Bill No.12 Total Carried Forward to Grand Summary					

GRAND SUMMARY OF BILL OF QUANTITIES		
BILL ITEM	DESCRIPTION	AMOUNT (Kshs)
	NOTE: ALL PRICES ARE VAT INCLUSIVE	
1	PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES	
4	SITE CLEARANCE AND TOPSOIL STRIPPING	
8	CULVERTS AND DRAINAGE WORKS	
10	GRADING AND GRAVELLING WORKS	
	GRAND TOTAL	