

EMC ROADS DEPARTMENT PROJECT;CULVERT INSTALLATION,KAPCHEMUTWA & KAMARINY WARDS

TARGET: 42M

BILL NO. 1: Supervision and support services					
ITEM	DESCRIPTION	UNIT	QTY	RATE(kshs)	AMOUNT(kshs)
BILL NO. 1:	Supervision and support services	LS	1	40,000.00	40,000.00
	Bill No. 1 Total Carried Forward to Grand Summary				40,000.00
BILL NO. 8: CULVERTS AND DRAINAGE WORKS					
	Note: No separate payments shall be made for gravel for blinding or hauling to spoil unsuitable excavation materials and the cost of such shall be included in the rates and prices				
8-60-01	culvert installation 900mm: Bed class 15/15, Wing walls , apron, Head wall and toe beam class 20/20,with surround class 20/20 and end structures reinforced with BRC A142 mesh including backfilling with approved material At kamworio-ngembasio (7m),kamaketoi-molem (7m),kabaigei-water supply (7m) primesacco-kiptabus (7m) At kameza-segut (9m),muno-sayori (7m)	M	42		
	Bill No. 8 Total Carried Forward to Grand Summary				

GRAND SUMMARY OF BILL OF QUANTITIES		
BILL ITEM	DESCRIPTION	AMOUNT (Kshs)
	NOTE: ALL PRICES ARE VAT INCLUSIVE	
1.00	PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES	40,000.00
8.00	CULVERT AND DRAINAGE WORKS	
	GRAND TOTAL	