

SAMBIRIR WARD

KOIBATEK WATER PROJECT 2017-18

PIPELINE (Nyirar Tobongon line)

Item	Description	Unit	Qty	Rate	Amount
01	Excavate and backfill trench minimum 600mm deep in normal soil	M	4518		
02	Provide and lay 40mm Ø GS pipe class B for river crossing and exposed area. Use approved jointing compound.	No	50		
03	Provide, handle, lay and joint 40mm PVC pipe class D using approved jointing compound(Tangit solvent cement)	No	703		
05	Provide and install the following fittings for places to be specified by the Engineer. <ul style="list-style-type: none"> • 40mmØ PVC adaptor • 40mmØ plain socket • 40mmØ union socket • 40mmØ 90° GS bend 	No No No No	12 6 4 4		
05	Provide and fix 40mmØ washout at lowest section along the line between Nyirar and Tobongon schools.	No	1		
	Sub Total to be carried to grand total				
06	add Project supervision	L/S	1	75,000	75,000
07	Add Project signage	L/S	1		
	GRAND TOTAL TO BE CARRIED TO FORM OF TENDER				

AMOUNT IN WORDS (KSHS).....
.....
.....

CONTRACTOR’S NAME.....

ADDRESS.....

SIGN.....

STAMP.....