

TARGET 12KM

BILL NO. 1: PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES					
ITEM	DESCRIPTION	UNIT	QTY	RATE(KSHS)	AMOUNT(KSHS)
	Brought forward from previous page.				
04.50.004	Allow a Prime cost of KShs. 100000 for supervision	PC Sum	PC	100,000	100,000.00
	Total carried forward to summary page				100,000.00
BILL NO. 4: SITE CLEARANCE AND TOPSOIL STRIPPING					
04.50.004	Clear site on road reserve including removal of all growths, bushes, hedges, trees, stumps, grub p roots approved material as directed by the Engineer	SM	22,000		
	Bill No. 4 Total Carried Forward to Grand Summary				
BILL NO. 10 - GRADING AND GRAVELLING WORKS					
	NOTE: No overhaul will be paid for separately under these items as it shall be deemed to have been included in the Contractor's rates				
10.50.001	Heavy Grading without watering or compaction	m ²	66,000		
10.70.002	Provide gravel wearing course- excavation, free haul, spread and compact gravel to a thickness 150mm	m ³	2,800		
	Bill No.10 Total Carried Forward to Grand Summary				
BILL NO 17 DRIFT CONSTRUCTION					
	Concrete				
17-60-001	Construct 4no. Drifts (15x5x0.2m) reinforced with BRC A142 MESH, Concrete class 20/20 as directed by the engineer	m ³	60		
	Total carried forward to summary page				
BILL NO.7: EXCAVATION AND FILLING FOR STRUCTURES					
07.50.001	Excavate for gabions in soft material	m ³	40		
08.80.001	Provide and place gabion boxes and mattresses where directed by the Engineer	No	10		
08.80.003	Rockfill to gabions	No	10		
	Total carried forward to summary page				

GRAND SUMMARY OF BILL OF QUANTITIES		
BILL ITEM	DESCRIPTION	AMOUNT (Kshs)
	NOTE:ALL PRICES ARE VAT INCLUSIVE	
1	Preliminaries and General Items	100,000.00
4	SITE CLEARANCE AND TOPSOIL STRIPPING	
10	Grading and gravelling works	
17	Drift construction	
7	Excavation and filling for structures	
	TOTAL	