

TARGET 12KM

| BILL NO. 1: PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES | | | | | |
|---|--|----------------|--------|------------|-------------------|
| ITEM | DESCRIPTION | UNIT | QTY | RATE(KSHS) | AMOUNT(KSHS) |
| | Brought forward from previous page. | | | | |
| 04.50.004 | Allow a Prime cost of KShs. 100000 for supervision | PC Sum | PC | 100,000 | 100,000.00 |
| | | | | | |
| | Total carried forward to summary page | | | | 100,000.00 |
| BILL NO. 4: SITE CLEARANCE AND TOPSOIL STRIPPING | | | | | |
| 04.50.004 | Clear site on road reserve including removal of all growths, bushes, hedges, trees, stumps, grub p roots approved material as directed by the Engineer | SM | 22,000 | | |
| | | | | | |
| | Bill No. 4 Total Carried Forward to Grand Summary | | | | |
| BILL NO. 10 - GRADING AND GRAVELLING WORKS | | | | | |
| | NOTE: No overhaul will be paid for separately under these items as it shall be deemed to have been included in the Contractor's rates | | | | |
| 10.50.001 | Heavy Grading without watering or compaction | m ² | 66,000 | | |
| 10.70.002 | Provide gravel wearing course- excavation, free haul, spread and compact gravel to a thickness 150mm | m ³ | 2,800 | | |
| | | | | | |
| | | | | | |
| | Bill No.10 Total Carried Forward to Grand Summary | | | | |
| BILL NO 17 DRIFT CONSTRUCTION | | | | | |
| | Concrete | | | | |
| 17-60-001 | Construct 4no. Drifts (15x5x0.2m) reinforced with BRC A142 MESH, Concrete class 20/20 as directed by the engineer | m ³ | 60 | | |
| | | | | | |
| | Total carried forward to summary page | | | | |
| BILL NO.7: EXCAVATION AND FILLING FOR STRUCTURES | | | | | |
| 07.50.001 | Excavate for gabions in soft material | m ³ | 40 | | |
| 08.80.001 | Provide and place gabion boxes and mattresses where directed by the Engineer | No | 10 | | |
| 08.80.003 | Rockfill to gabions | No | 10 | | |
| | | | | | |
| | Total carried forward to summary page | | | | |

GRAND SUMMARY OF BILL OF QUANTITIES

| BILL ITEM | DESCRIPTION | AMOUNT (Kshs) |
|-----------|---|---------------|
| | NOTE: ALL PRICES ARE VAT INCLUSIVE | |
| 1 | Preliminaries and General Items | 100,000.00 |
| 4 | SITE CLEARANCE AND TOPSOIL STRIPPING | |
| 10 | Grading and gravelling works | |
| 17 | Drift construction | |
| 7 | Excavation and filling for structures | |
| | TOTAL | |