

EMC ROADS DEPARTMENT 2016-2017 PROJECT  
 MAINTENANCE OF MSEKEKWA-KAPSOYO-KENDUR ROAD, KAPCHEMUTWA WARD

BILL NO. 1: PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES					
ITEM	DESCRIPTION	UNIT	QTY		AMOUNT
	<b>Brought forward from previous page.</b>				
1.01	Allow a Prime cost of KShs. 200000 for supervision	PC Sum	PC	200,000	200,000.00
1.02	Provide, erect and maintain publicity signs as directed by the Engineer	No.	2		
	<b>Bill No.12 Total Carried Forward to Grand Summary</b>				

BILL NO. 4: SITE CLEARANCE AND TOPSOIL STRIPPING					
ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
4.01	Clear site on road reserve including removal of all growths, bushes, hedges, trees, stumps, grub roots and other deleterious materials as directed by the Engineer	SM	12,000		
	<b>Bill No. 4 Total Carried Forward to Grand Summary</b>				

BILL NO. 8: CULVERTS AND DRAINAGE WORKS					
ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<b>Note: No separate payments shall be made for gravel for blinding or hauling to spoil unsuitable excavation materials and the cost of such shall be included in the rates and prices</b>				
8.08	Excavate for culvert, supply and/or install 900 mm diameter, bed class 15/15, wingwalls apron, headwalls, toe beam and surround class 20/20 and end structures reinforced with BRC A142 mesh including backfilling with the approved material	M	56		
	<b>Bill No. 8 Total Carried Forward to Grand Summary</b>				

BILL NO. 12: NATURAL MATERIAL SUBBASE AND BASE					
ITEM	DESCRIPTION	UNIT	QTY	RATE(KSH)	AMOUNT(KSH)
	<b>NOTE: No overhaul will be paid for separately under these items as it shall be deemed to have been included in the Contractor's rates</b>				
12-50-01	Heavy Grading without watering or compaction	m2	70,700		
12-60-02	Provide Gravel wearing course, spread and compact to a thickness of 150mm.	m3	900		
	<b>Bill No.12 Total Carried Forward to Grand Summary</b>				

BILL NO. 22: DAYWORKS					
ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
22.13	Dozer 230-325 HP	hr.	200		
	<b>Bill No.12 Total Carried Forward to Grand Summary</b>				

GRAND SUMMARY OF BILL OF QUANTITIES		
BILL ITEM	DESCRIPTION	AMOUNT (Kshs)
	<b>NOTE: ALLPRICES ARE VAT INCLUSIVE</b>	
1	Preliminaries and General Items	
4	Light bush clearing on the road reserve including removal of all growths, bushes, trees and other materials	
8	Culverts and Drainage Works	
12	Natural Gravel Base and Heavy Grading	
22b	Dozzer works	
	<b>TOTAL</b>	