

EMC ROADS DEPARTMENT 2017-2018 PROJECT.MAINTENANCE OF BIRIRWOK-CHEPTUYA-CHEBIEMIT ROAD IN MOIBEN KUSERWO
WARD

TARGET: 1.5KM

ITEM	DESCRIPTION	UNIT	QTY	RATE(KSHS)	AMOUNT(KSHS)
BILL NO. 1: PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES					
1.01	Allow a Prime cost of KShs 10,000 for supervision	LS	1	10,000	10,000.00
1.02	Provide, erect and maintain publicity signs as directed by the Engineer	No.	1		
	Total carried forward to summary page				
BILL NO. 4: SITE CLEARANCE AND TOPSOIL STRIPPING					
04-50-004	Light Bush Clearing	SM	1,500		
	Bill No. 4 Total Carried Forward to Grand Summary				
BILL N MAINTENANCE OF BIRIRWOK-CHEPTUYA-CHEBIEMIT ROAD IN MOIBEN KUSERWO WARD					
	Note: No separate payments shall be made for gravel for blinding or hauling to spoil unsuitable excavation materials and the cost of such shall be included in the rates and prices				
08-60-020	New Culvert Installation-600mm Hounded, With wingwall apron,headwalls and toe beam reinforced with BRC A142 Mesh	M	6		
	Bill No. 8 Total Carried Forward to Grand Summary				
BILL NO. 10: GRADING AND GRAVELLING WORKS					
10-50-001	Heavy grading without watering or compaction	SM	7,000		
	Bill No.12 Total Carried Forward to Grand Summary				

GRAND SUMMARY OF BILL OF QUANTITIES		
BILL ITEM	DESCRIPTION	AMOUNT (Kshs)
	NOTE: ALL PRICES ARE VAT INCLUSIVE	
1	PRELIMINARY AND SUPERVISORY/SUPPORT SERVICES	
4	SITE CLEARANCE AND TOPSOIL STRIPPING	
8	CULVERTS AND DRAINAGE WORKS	
10	GRADING AND GRAVELLING WORKS	
	GRAND TOTAL	